GUIDANCE FOR THE SURVEY AND CONSTRUCTION OF STEEL SHIPS

Part N

Ships Carrying Liquefied Gases in Bulk

2009 AMENDMENT NO.1

Notice No.18 15th April 2009

Resolved by Technical Committee on 4th February 2009

Notice No.18 15th April 2009 AMENDMENT TO THE GUIDANCE FOR THE SURVEY AND CONSTRUCTION OF STEEL SHIPS

"Guidance for the survey and construction of steel ships" has been partly amended as follows:

Part N SHIPS CARRYING LIQUEFIED GASES IN BULK

N4 CARGO CONTAINMENT

N4.10 Construction and Testing

N4.10.14 Gas-trial and Cargo Full Loading Test

Table N4.10.14-2 has been amended as follows.

Table N4.10.14-2 Survey Items of Full Loading Test

1 abic 1(4,10,14-2	but vey items of run Loading Test
	Survey items
1. At loading operation 1)	Continuous loading rate
	Proper operation of gas detection systems 4)
	Proper operation of cargo control and monitoring systems such as level
	gauging equipment, temperature sensors, pressure gauges, cargo pumps,
	compressors and cargo heat exchangers 4)
	Proper operation of over-flow control systems 4)
	• Proper operation of nitrogen generating plants or inert gas generators and
	pressure control systems for insulation, interbarrier and annular spaces 4)
	Proper operation of cofferdam heating systems, if fitted ⁴⁾
	Proper operation of reliquefaction plants, if fitted 4)
	• Proper operation of equipment fitted for the burning of cargo vapours 4)
	On-deck cargo piping system
	Topping off process for cargo tanks including proper operation of high
	level alarms
2. Condition of eargo tanks and other eargo	Cargo tanks and supports
eontainment systems a After full loading or	Hull adjacent to cargo tanks (cold spot)
during voyage 2)	Insulation capacity of cargo tanks and supports (cold spot)
	Atmosphere in hold spaces
	<u>Capacity of pressure/temperature indicator</u>
3. During voyage 2)	- Insulation capacity of cargo tanks and supports (cold spot)
	- Cold spot on the construction adjacent to cargo tanks
	Capacity of pressure/temperature indicator

43. At discharging operation 3)	Emergency shutdown system testing prior to commencement of
4 <u>5</u> . At discharging operation	
	unloading
	Discharging rate
	Conditions of related installations such as those listed in 1.
	On membrane vessels, verification that the readings of the cofferdam and
	inner hull temperature sensors are not below the allowable temperature
	for the selected grade of steel
	On-deck cargo piping system
	Other operation of discharging
	Submission/Survey of related records such as cold spot examination
	records ⁶ , cargo logs, operation logs of installations related to cargo
	operations and alarm reports where no attendance during the cargo loaded
	voyage of <u>32</u> .

Note

- 1) Priority is to be given to latter stages of loading (approximately last 6 *hours*).
- 2) May be exempted from witness the presence of the Surveyors. In such cases, each survey item is to be recorded in order that the Surveyors can check this record.
- 3) Priority is to be given to the commencement of unloading (approximately first 4-6 *hours*).
- 4) Overall inspection may be accepted where an installation are not in operation.
- 5) In case where implementation is difficult, the verification of operation may be made by suitable other method.
- 6) Surveyors are to check the sampling of cold spot records, if possible.

N6 MATERIALS OF CONSTRUCTION

N6.1 General

Paragraph N6.1.4 has been added as follows.

N6.1.4 Impact Test

The wording "To be in accordance with Recognized Standard" referred to in the requirements given 6.1.4-1, Part N of the Rules means to refer to note (6) of Table K4.28.

EFFECTIVE DATE AND APPLICATION

1. The effective date of the amendments is 15 April 2009.